

GARHWAL MANDAL VIKAS NIGAM LIMITED

74/1, Rajpur Road, Dehradun

Tender Form

I/we do hereby tender to execute the **DEVELOPMENT WORK AT GAUCHER DISTT. CHAMOLI.** More particularly describe in schedule “B” specification etc. attached with this tender form and deposit herewith an earnest money the sum of **₹ 2,62,000.00 (₹ Two lac sixty two thousand only)** The earnest money may be forfeited if I/we fail to sign the contract for the work, the form of which I/we have received within the time specified in the notice calling for tenders.

2. With this tender I/we submit a schedule of rates upon which our tender has been based and I/we aware that the corporation accept no responsibility for the accuracy of the bill quantities supplied with the form of tender and condition of the contract.

3. I/we have given below my/our permanent postal address. Any change in the address shall be intimated from time to time in writing to the Engineer In charge. I/we shall make necessary arrangement at all time to receive any notice, order and communication that will be issued to me/us at this address. If any letter/communications is received back undelivered. Nigam will be free to take any action in view of the same without entitling me/us for any claims whatsoever in this account.

Signature of Tenderers

Signature of witness

Address.....
.....
Dated.....

1)
Address
.....
2)
Address

The above tender is hereby accepted by me on behalf of Garhwal Mandal Vikas Nigam Ltd.

GENERAL MANAGER

Dated.....the day of

dora/ tender form & cond/ conditions

SCHEDULE "B" FOR CIVIL WORKS

Date of Calling Tender: 11.11.2011
 Date of Receiving Tender: 3.12.2011
 Date of Opening Tender: 3.12.2011

Time of Completion: 10 month
 Earnest Money: Rs. 2,62,000.00
 Cost of Tender Form: Rs. 2000.00+ Trade Tax

NAME OF WORK: DEVELOPMENT WORK AT GAUCHER DISTT. CHAMOLI.

S.No.	NAME OF ITEM	QTY	UNIT	RATE	AMOUNT
1	Excavation in foundation in all type of soils including up to 1.5M lift and lead upto 30M and including filling watering and ramming of excavated earth into the trenches are in to the space between the building and sites of foundation trenches or in to the plinth and removal and disposal of surplus earth as directed by the Engineer-in-charge upto a distance of 30M from the foundation trenches.	3183.00	Cum		
2	Concrete with 40mm gauge approved stone ballast, local sand and cement in proportion of 8:4:1 in foundation including supply of all material, labour and T&P etc. required for proper completion of the work.	322.00	Cum		
3	Concrete with 40mm gauge approved stone ballast, local sand and cement in proportion of 6:3:1 in foundation including supply of all material, labour and T&P etc. required for proper completion of the work.	11.00	Cum		
4	P.C.C 1:2:4 cement coarse sand and 20 mm gauge stone ballast in hold fast including supply of all labour, material etc.	45.00	Cum		
5	Tor Steel work in plain work such as in R.C.C work brought to required shape as necessary including binding for proper completion of the work. S.I. No. 314	257.00	Qtl		
6	R.R. stone masonry 1:6 cement, sand mortar in R/w and B/w including all labour, material T & P etc .S.I. No. 516	316.00	Cum		
7	Random coursed Rubble stone masanary 1:6 cement and fine sand mortar in foundation and plinth of building including supply of all material, labour, T & P etc. required for proper completion of the work	31.00	Cum		
8	Painting and varnishing on new iron works in small area are new work with one coat priming and two coat of paint or varnish including supply of all material, labour, T&P etc. required for proper completion of the work.	674.00	Sqm		
9	16 mm thick plaster with 1:6 cement and fine sand mortar on smooth surface including supply of all material, labour and T&P etc. required for proper completion of the work.	100.00	Sqm		
10	Earth work in excavation in general cutting in ordinary soil.	235.00	Cum		
11	R.C.C. Work with cement, approved coarses sand and 2cm gauge approved stone ballast in proportion of 1:1.5:3 in RAFT FOUNDATION & FOOTING excluding supply of reinforcement & its bending but including its fixing and binding the same with with 24 B.W.G. binding wire and including necessary centering and shuttering including supply of all material, labour and T&P etc. required for proper completion of the work.	35.00	Cum		

S.No	NAME OF ITEM	QTY	UNIT	RATE	AMOUNT
12	Same as item no. 11 but R.C.C 1:1.5:3 in lighter beam having span up to 6 mtr.	71.00	Cum		
13	Same as item No. 11 but R.C.C 1:1.5:3 in T-beam slab roofs and R.C.C columns complete in all respect.	226.00	Cum		
14	MS or iron work in heavy sizes such as in roof trusses, purlins, rafters, MS square/round/D shape pipe railings etc. wrought to required form, including drilling holes rivetting or welding where necessary and also including supply of steel bolts, nuts etc and their fixing required for proper completion of the work.	56.00	Qtl		
15	P/L of 60mm thick M-35 interlocking blocks of approved shape including supply of all materials, labour T & P etc. required for proper completion of the work.	435.00	Sqm		
16	Sand filling below interlocking blocks including supply of all materials, labour T & P etc. required for proper completion of the work.	44.00	Cum		
17	S/F of 25mm thick kota stone size 60cm x 60cm for flooring over 20mm thick back of cement mortar 1:4 cement and coarse sand laid over joint with gray cement slurry including all labour, material, T&P etc. complete	73.00	Sqm		
18	H.P stone filling in back of retaining walls including all material, Labour T & P etc. S.I. No. 164	151.00	Cum		
19	Filling earth and stone in plinth including watering , dressing, ramming etc. S.I. No. 161	16.00	Cum		
20	S/F of 25mm thick Red stone size 60cm x 60cm for flooring over 20mm thick back of cement mortar 1:4 cement and coarse sand laid over joint with gray cement slurry over 8cm thick P.C.C 1:4:8 base concrete including all labour, material, T&P etc. complete	1100.00	Sqm		
21	S/F of Swiss Chalets 4.60mtr x 9mtr complete with fixtures, water proofing, PVC and heat sealing complete as per specification and direction of E/I	6.00	Nos		
22	Powder coated trough mild steel sheet roofing 0.63mm fix in position including punching hole fixed with J & U bolts 10mm dia GI limpet washers etc. including supply of all material labour T&P etc required for proper completion of the work	117.00	Sqm		
23	S/F of 22 B.W.G. ridges for powder coated mild steel sheet roofing including punching holes and supply of J and U bolts, nuts limpet and bitumin washers complete including supply of all material labour T&P etc required for proper completion of the work	70.00	Rmtr		
24	Supply of three seater Garden benches of size 5'x2'x32" made with cast iron sides and seat, back made with 1½"x ¾" M.S. pipe as per approved drawing and design including one coat of red oxide primer & 2 coat of painting and provision for Nut, Bolt etc for proper fixing inclusive of all taxes.	10.00	Nos		

S.No	NAME OF ITEM	QTY	UNIT	RATE	AMOUNT
25	Land Scapping work including cutting & screening of soil, filling with screened earth, surface dressing of ground, removing of vegetation and inequalities not exceeding 150mm depth, disposal of rubbish upto 50m lead and 1.5m lift, providing and applying of organic manure (cow dung) uniformly spreading over the prepared surface , profiling work for depth of about 6" , providing earth blanket turf of quality local turf of minimum 30cm x 30 cm x 7.5cm size including transportation from the authorised area to the work site, planting of subtropical and temperate flowering plants, flowering trees, tree fern, bamboos, decorative garden plants and trees, 1 tree per average 10 sqm including preparation of bed and manuring, watering etc complete as per direction of engineer Incharge.	2040.00	Sqm		

Note: I/We tender at the Item wise Rate entered in the schedule 'B' above after taking fully into consideration that the rates are inclusive of all leads, lifts, Royalty and other incidental expenses and that be rates are for finished item of works

Quantities given in the schedule'B' may be deleted or varied widely without untitling the contractor for any compansation in this respect.

All works shall be carried out strictly as per detailed specification

Sale tax shall be deducted from gross amount of the bill.

officer
Issuing
Tender

Contractor

officer
opening
Tender

officer
Recommending
Tender

officer
accepting
Tender

गढ़वाल मण्डल विकास निगम लिमिटेड में भवन निर्माण कार्यों हेतु निविदा डाले जाने हेतु नियम एवं शर्तें

1. निविदा में दरें स्याही से शब्दों तथा अंकों में अंकित की जानी चाहिए, कम अंकित दर ही मान्य होगी।
2. निविदा प्रपत्र के साथ रु0 100.00 के स्टाम्प पेपर पर एक रूपये का रसीदी टिकट लगाकर हस्ताक्षर कर सलंगन करना आवश्यक है जिस पर यह अंकित हो कि निविदा की वैधता की निर्धारित अवधि से पूर्व यदि वह अपने निवेदन को वापस लेता है तो उसके द्वारा जमा की गई धरोहर राशि जब्त कर ली जायेगी।
3. धरोहर राशि राष्ट्रीयकृत बैंक की नवीनतम एफ0 डी0 आर0/सी0 डी0 आर0/राष्ट्रीय बचत पत्र /किसान विकास पत्र के रूप में अधोहस्ताक्षरी के पक्ष में देय होगी।
4. आयकर एवं व्यापारकर की कटौती नियमानुसार की जायेगी तथा प्रत्येक वित्तीय वर्ष समाप्ति के एक माह के अन्दर कटौती के प्रमाण पत्र ठेकेदार/फर्म कार्यालय से अवश्य प्राप्त कर लें, विलम्ब के लिए विभाग उत्तरदायी नहीं होगा।
5. सर्शत एवं अपूर्ण निविदायें मान्य नहीं होगी।
6. निविदादाता निविदा डालने से पूर्व स्वयं स्थल निरीक्षण कर लें अन्यथा इस सम्बन्ध में कोई क्लेम मान्य नहीं होगा।
7. अधोहस्ताक्षरी को किसी भी अथवा समस्त निविदाओं को बिना कारण बताये, निरस्त करने का अधिकार सुरक्षित है।
8. साझेदारी में दी गई निविदा के साथ सत्यापित पार्टनरशिप डीड सलंगन करना अनिवार्य है।
9. निविदा में मदों की मात्रा आवश्यकतानुसार घटाई/बढ़ाई/समाप्त की जा सकती है जिसका कोई अतिरिक्त क्लेम मान्य नहीं होगा।
10. विभाग द्वारा ठेकेदार को कोई निर्माण सामग्री उपलब्ध नहीं करायी जायेगी। यदि कोई निर्माण सामग्री उपलब्ध करायी जायेगी तो उसकी कटौती नियमानुसार बिल से की जायेगी।
11. सीमेंट 43 ग्रेड ओ0पी0सी0, आई0एस0 8112-1989 के अनुरूप ए0सी0सी0/सी0सी0आई0/अम्बुजा/विक्रम को प्रयुक्त किया जायेगा।
12. Fe 415TMT Bar (SAIL/ TATA TISCON / RINL) आई0एस0 1786-1986 के अनुरूप प्रयुक्त किया जायेगा तथा प्रत्येक लॉट का टैस्ट सर्टिफिकेट देना आवश्यक है।
13. निर्माण कार्य हेतु कार्य स्थल पर पानी / विद्युत की व्यवस्था ठेकेदार को स्वयं करनी होगी। इसमें विभाग की कोई जिम्मेदारी नहीं होगी तथा इस मद में अलग से कोई भुगतान नहीं किया जायेगा।
14. निविदादाता को निविदा के साथ व्यापारकर व ई0पी0एफ0 पंजीकरण प्रमाण पत्र तथा पेन कार्ड की छाया प्रति संलग्न करना अनिवार्य है।
15. विभाग /उत्तराखण्ड शासन की तकनीकी जाँच समिति अथवा उच्चाधिकारियों द्वारा कार्य गुणवत्ता में कमी के कारण यदि कोई वसूली प्रस्तावित की जाती है, तो वह ठेकेदार से की जायेगी एवं निर्माण कार्य की जाँच हेतु की गयी तोड़-फोड़ को ठीक करने का कार्य सम्बन्धित ठेकेदार द्वारा ही किया जायेगा।

प्रधान प्रबन्धक (निर्माण)
गढ़वाल मण्डल विकास निगम लि0
74/1 राजपुर रोड, देहरादून।

dora/ tender form & cond/ conditions